


## PROPOSAL

Trent Sorensen Cell: 801.960.5408 Office: 801.631.3873 Trent@zioneng.us		Zion Engineering PO Box 136 Riverton, Utah 84065 State Contract#MA4798
--	---	---

**Contact**

Joey Jones  
 801-850-1682  
 Provo School District Office  
 280 West 940 North, Provo, UT 84604

Apr 6, 2026  
**Quote # 1501**

**Scope of Work**

Specific Details

Provide labor and materials to replace twenty-three (23) rooftop units (RTUs) of various sizes at the District Office main building, replacing all existing units with the exception of one (1) RTU. This scope includes units located over the gym and offices across the courtyard.

Scope includes:

- Removal and proper disposal of existing RTUs
- Supply and installation of new replacement RTUs
- Replacement units sized in accordance with current equipment availability and project requirements
- System startup, testing, and commissioning to verify proper operation

Unit Breakdown (Per Proposal):

- Seventeen (17) – 2-ton units (note: 1.5-ton units are no longer manufactured; units have been upsized accordingly)
- Two (2) – 2.5-ton units
- Two (2) – 3-ton units
- One (1) – 5-ton unit
- One (1) – 6-ton unit
- One (1) – 12.5-ton unit (Gym Roof)

**Default Section** \$205,319.90

Material Description	Qty	Unit Price	Subtotal
RTU Equipment 23 Units	1	\$168,857.14	\$168,857.14
Crane	1	\$6,571.43	\$6,571.43
Electrical, Controls, Misc	23	\$485.71	\$11,171.33
		<b>Material Total</b>	<b>\$186,599.90</b>
Labor	Qty	Unit Price	Subtotal
Local 312 - Technician	160	\$117.00	\$18,720.00
		<b>Labor Total</b>	<b>\$18,720.00</b>

	<b>Sub Total</b>	\$205,319.90
	<b>Quote Total</b>	\$205,319.90

**Exclusions**

- Items or Labor not specifically mentioned above are EXEMPT from this proposal. Such as: Drywall patchwork, pre-existing conditions, general construction, and electrical, not specifically mentioned in the scope above.

**Notes:**

- Job to be completed during regular hours 08:00-16:30 Monday to Friday
- Pricing is subject to parts availability and all items being done concurrently

**Customer Acceptance:**

---

---

Type/Print Name  
(Signature)

Customer Acceptance

---

Title