



CUSTOMER INFORMATION

Project: Luling HS Softball Field
Location: 218 E Travis St Luling TX

DATE 7/7/2026
Quote # 22286.15
Proposal valid for: 15 Days
Prepared by: Joe Palomino

4 Pole Tieback Backstop System		
(30' Tall x 104' Wing x 20' Backstop x 104' Wing) [Net = 104' Wing x 20' Backstop x 48'-6" Wing] Features: 3 – 14" Steel Poles, 37' AGL + 12' Embedment in 36" Dia. Hole, Black finish (1.71 C/Y of 2500 PSI Concrete needed for each pole.) 1 – 18" Steel Poles (1B end), 37' AGL + 14' Embedment in 30" Dia. Hole, Black finish (1.63 C/Y of 2500 PSI Concrete needed for each pole.) *Concrete not included, for est. purposes 4,900 SF of #36 Knotted Nylon Netting UV treated Black -Engineering Included -		
	Total:	\$104,439.00
Fusion Wall		
Product Details: Dimensions: 36"H x 117LF ¾" Weather treated sheathing backed, 3" high impact foam Wrapped in 18oz all weather vinyl. Color: TBD Fusion hardware- Strut Channel, Straps, and Zeus Clip 2.5" Posts set approximately 4'OC Additional charge for UV Coated Digital Print Graphics Remove and Dispose of Existing Chain Link Back Stop		
	Total:	\$18,397.00
Dugout Rail System - 1st Base		
Product Details: Dimensions: 6'H x 36'L (includes mid & bottom rail) Railing: 2"x2" 11 gauge Sq Steel Tube Posts and Rails with 3/8"x7"x7" Base Plates. Industrial Black Paint Finish. 3/8"x4" LDT Padding: ¾" Weather treated sheathing backed padding with 1.5" high impact foam. Wrapped in 18oz all weather vinyl. Color: TBD. U Pads for top rail and end posts. Flat Pads for interior posts. Netting: #18 Knotted Dyneema		
	Total:	\$11,750.00

Dugout Rail System - 3rd Base		
Product Details: Dimensions: 6'H x 26'L (includes mid & bottom rail) Railing: 2"x2" 11 gauge Sq Steel Tube Posts and Rails with 3/8"x7"x7" Base Plates. Industrial Black Paint Finish. 3/8"x4" LDT Padding: 3/4" Weather treated sheathing backed padding with 1.5" high impact foam. Wrapped in 18oz all weather vinyl. Color: TBD. U Pads for top rail and end posts. Flat Pads for interior posts. Netting: #18 Knotted Dyneema		
	Total:	\$9,707.00
Fielders Choice Elite Cantilever Dugouts (10' x 40') (QTY2)		
Product Details: All Steel pre-engineered structure. Includes 6"x4" plated mounted columns, roof rafters and beams and 24 gauge dent resistant metal roof panels. Frame finish is industrial paint. Color: TBD. Roof panel & trim color: TBD 10 year parts and hardware warranty. 40 year finish warranty.		
Provide and Install (2) new 7' Tall X 60' Total (10' X 40' X 10') CMU Wall at Dugouts		
Remove and Dispose of Existing Dugouts and Concrete		
	Total:	\$122,225.00
Dugout Equipment - Home Side ONLY		
<u>Eagle Players Bench</u>		
Product Details: All Steel pre-engineered structure. Includes 6"x4" plated mounted columns, roof rafters and beams and 24 gauge dent resistant metal roof panels. Frame finish is industrial paint. Color: TBD. Roof panel & trim color: TBD 10 year parts and hardware warranty. 40 year finish warranty.		
<u>12 Helmet Cubby Rack</u>		
Product Details: Rack holds 12 helmets 3 tall x 4 wide cubby layout 36"H x 42-3/4"W x 11-1/4"D Painted in color(s) of choice		
<u>Angles 15 Bat Rack</u>		
Product Details: Angled rack holds 15 bats 16"H x 34-3/4"W x 11"D Painted in color of choice Includes a team logo		
	Total:	\$8,233.00

Bleachers		
Non-Elevated 5 Row x 33' Bleacher (QTY 2)		
Product Details: Model: DLW 5-33 Aluminum angle understructure 8" rise x 24" run 2x10 anodized seat planks Double 2x10 footboards Chain link guardrail system Seating capacity: 94		
Elevated 10 Row x 21' Bleacher (QTY1)		
Product Details: Model: DLWE 10-21 Aluminum angle understructure 8" rise x 24" run 2x10 anodized seat planks Double 2x10 footboards Chain link guardrail system 54" wide front walkway elevated 32" above grade w/ stairs at each end Seating capacity: 104		
	Total:	\$77,069.00
7 X 10 Elevated Metal Pressbox		
Fabrication and installation of a structural steel support system designed to elevate the press box floor above bleachers Construction of a 7' x 10' press box utilizing R-panel metal for the exterior walls and roof. Pressbox to be Enclosed with (1) Single Door and (1) Pull up Window No HVAC equipment, insulation or Electricity. Framed roof system with matching R-panel roofing. Structural floor system designed to support typical press box occupancy and equipment. All fasteners, trim, flashing, Concrete, Site Work and miscellaneous materials Included for a complete installation. Prime and paint exposed structural steel (or galvanized steel if specified).		
	Total:	\$82,961.00
Concrete Slab		
1. Provide and Install 4" Thick Concrete Slab Behind Home Plate and in Both Bleacher Areas Roughly 3,105 Sq Ft		
	Total:	\$58,219.00
	Total Bid:	\$493,000.00
Proposal Exclusions		
Core Drilling, Final Layout of Fence, Utility Locate and Grounding and Bonding.		

Note: Any changes, alternates, and/or add ons will be performed in writing and signed by both General Contractor and Encore Fence.

1803 W Ave. D
Temple, TX 76504
www.encoretx.com

Office: 254-218-3310
Email: jpalomino@encoretx.com