



Owner Contingency Modification

0309b. - Stillwater New High School

Title: OMOD 85 - RFI 233 Island Electrical Room 1075

Owner Contingency Modification : # 85
Date: 11/12/2025 **Date Required:**

Description of Work: The following scope of work is included in this PCO:
 1. Provide additional electrical circuitry for the island oven in Room 1075A as outlined in RFI 233.


The below items will increase or decrease the contract scheduled value by the amounts listed below. Time in days indicates additional time required to project completion due to the changes referenced.

| Item | Units | UM | Unit Price | Item Total | Bonds & Ins | Fee | Total | Time (In days) |
|---|-------|----|------------|------------|-------------|------|------------|----------------|
| 1 : OMOD 85 - RFI 233 Island Electrical Room 1075 | 0.00 | LS | 0.00 | - 4,773.8 | 0.0 | 0.00 | - 4,773.75 | |
| 2 : Colburn Electric | 0.00 | LS | 0.00 | 4,773.8 | 0.0 | 0.00 | 4,773.75 | |

Total Change Amount: 0.00

Notes:

Approved By:

| | |
|---|------------|
|  | 11/19/2025 |
| Construction Manager: | Date: |
|  | 11/19/2025 |
| Architect: | Date: |
|  | 11/20/25 |
| Owner: | Date: |

Job ID: EW00541



Project: STILLWATER HIGH SCHOOL BUILDING

CO: 43: RFI 233 kitchen power again

Takeoff

Phase: BRANCH

| Item # | Qty | U/ | Q/M | Size | Description | Material Result | Labor Result |
|--------|--------|----|-----|------------------|--|-----------------|--------------|
| TITLE | 168.00 | EA | M | 3/4 | EMT ON BAR JOIST MULTI RUN | 0.00 | 0.00 |
| 10001 | 168.00 | FT | M | 3/4 | EMT | 145.39 | 11.25 |
| 20011 | 0.00 | EA | M | 3/4 | EMT 90-ELBOW | 0.00 | 0.00 |
| 20001 | 2.00 | EA | M | 3/4 | EMT FIELD-BEND | 0.00 | 0.58 |
| 30001 | 16.00 | EA | M | 3/4 | EMT STEEL-SS COUPLING | 9.87 | 1.00 |
| 630075 | 23.00 | EA | M | 3/4 | COND HAMMER-ON HGR 1/4-FLNG SNP-CLOSE HD | 66.23 | 1.85 |
| 30011 | 4.00 | EA | M | 3/4 | EMT STEEL SS CONNECTOR | 2.18 | 0.63 |
| 40001 | 4.00 | EA | M | 3/4 | PLASTIC BUSHING | 0.63 | 0.71 |
| 70034 | 634.00 | FT | M | 10 | THHN/THWN CU (STR) | 197.74 | 4.53 |
| 100032 | 6.00 | EA | M | #18 to 8 | WIRE-NUT MED -RED | 1.23 | 0.63 |
| 70229 | 174.00 | FT | M | 10. | GREEN THHN CU (GRD 60A) | 55.38 | 1.77 |
| 100032 | 2.00 | EA | M | #18 to 8 | WIRE-NUT MED -RED | 0.41 | 0.21 |
| 150041 | 2.00 | EA | M | 2-1/8"D | 1900 CMB-KO NO BRKT | 5.72 | 0.63 |
| 150096 | 2.00 | EA | M | | 1900 BLANK COVER | 1.66 | 0.21 |
| 630577 | 2.00 | EA | M | 1/4" FLANGE | HAMMER-ON FLANGE CLIP - 1/4-20 x | 4.22 | 0.13 |
| 630505 | 2.00 | EA | M | THREAD ROD MOUNT | COMB BOX & 1/2 > 3/4" SNP-CLS | 26.14 | 0.79 |
| 161526 | 2.00 | EA | M | 1/4-20 | PLTD HEX NUTS | 0.10 | 0.06 |
| 160873 | 2.00 | EA | M | 1/4" | PLTD FLAT WASHER | 0.13 | 0.00 |
| 100053 | 2.00 | EA | M | #12 SOL | 8" PIGTAIL W/GRD SCREW | 1.52 | 0.21 |
| 180242 | 1.00 | EA | M | 30/2 | BOLT-ON BREAKER | 36.00 | 0.87 |
| 140127 | 1.00 | EA | M | 30A 3P4W | FLUSH RECEPT 250V N14-30R | 6.41 | 0.67 |
| 140836 | 1.00 | EA | M | 20>30A 1.6" HOLE | 1G STN-STL SGL RECEPT PLATE | 3.60 | 0.15 |
| TITLE | 1.00 | EA | M | #10 1/2" EMT | 20A 1G DX COML TR | 0.00 | 0.00 |

