



ESTIMATE	#16875
ESTIMATE DATE	May 13, 2026
SERVICE DATE	May 13, 2026
EXPIRATION DATE	Jun 11, 2026

## Steve's Plumbing & Excavating, LLC

Vienna Township  
3400 W. Vienna Road  
Clio, MI 48420

(810) 686-7580  
mfalardeau@viennatwpqc.gov

CONTACT US  
1212 N Genesee Rd  
Burton, MI 48509

(810) 742-4270  
stevesplumbingofficemi@gmail.com

### ESTIMATE

#### Spot Repair

##### Services

##### Excavating Service - Service

- Call Miss Dig
- Excavate where existing pipe is flagged
- Install approximately 10' of 4" SCH 40 PVC
- Install proper fittings
- Install a new connection onto existing down spout located in the SE corner of building
- Back fill and rough grade excavated area

##### Note:

- Miss Dig is needed in the front of the building starting to the right side of the double doors entryway to the east of the lower level storm structure.
- There is a sprinkler system and parking lot lighting in the area where work is being done.

##### Important - Information Regarding Your Service:

- 50% deposit due in order to schedule
- Remaining 50% due the day of the plumbing service
- Can be paid in cash, check, ACH, or Credit Card  
(3% non-cash adjustment applies to credit cards)  
(Credit Cards and ACH can be paid on our website STEVESPHC.COM)

Services subtotal: \$4,350.00

Subtotal \$4,350.00

Tax (MI 6%) \$0.00

**Total \$4,350.00**

#### Sump Line Replacement

##### Services

##### Excavating Service - Service

- Call Miss Dig
- Excavate from where the 2 of the 3 downspouts on the front right side of the building are connecting
- Replace S&D pipe connecting 2 of the 3 downspouts on the front right side of the building with 4" sch40 PVC
- Install approximately 130' of 4" sch40 PVC
- Haul away debris
- Backfill and rough grade

##### Note:

- Miss Dig is needed in the front of the building starting to the right side of the double doors entryway to the east of the lower level storm structure.
- There is a sprinkler system and parking lot lighting in the area where work is being done.

##### Important - Information Regarding Your Service:

- 50% deposit due in order to schedule
- Remaining 50% due the day of the plumbing service
- Can be paid in cash, check, ACH, or Credit Card  
(3% non-cash adjustment applies to credit cards)  
(Credit Cards and ACH can be paid on our website STEVESPHC.COM)

Services subtotal: \$4,600.00

Subtotal	\$4,600.00
Tax (MI 6%)	\$0.00
<b>Total</b>	<b>\$4,600.00</b>

Conveniently Pay Your Bill on our Website STEVESPHC.COM

All Credit Card Transactions are subject to a 3% Non-Cash Adjustment. All Cash, Check, and ACH Transactions have no additional fee.  
We now have financing options available @ <https://www.enhancify.com/stevesphc>

Any estimate over \$1000 requires a 50% deposit in order to schedule the service. In the event that a job is canceled for any reason after it has been scheduled, \$100 will be withheld from the refund.

Steve's Plumbing and Heating, LLC offers a 1-year labor warranty that starts the day the job is finished but cannot be honored if the bill is not paid in full.

Please note: Steve's Plumbing and Heating, LLC only installs quality parts that we trust will last. Any repairs which the client purchases parts to complete the service will not include a labor warranty unless the technician is found at fault. Additionally, there is no warranty when the client chooses to have the technician perform a service against the technician's recommendation. Steve's Plumbing and Heating, LLC is not responsible for anything that cannot be identified by miss dig.

NOTICE: Steve's Plumbing and Excavating, LLC, is not responsible for cleaning or restoring the interior or exterior of the property. This includes, but is not limited to, grass seed, straw, topsoil, or any other property restoration that is not included in the estimate.

We appreciate your business! Thank you!!