



Robin Faye Lindeen Blakeley <rlindeen@corbett.k12.or.us>

Radon Mitigation Update and Post-Mitigation Test Results – CMS Woodard Campus

1 message

Brie Windust <bwindust@corbett.k12.or.us>
To: All District List <alllist@corbett.k12.or.us>

Wed, Jul 8, 2026 at 11:30 AM

Dear Corbett Staff and Families,

Following the installation of a permanent radon mitigation system, the building underwent post-mitigation testing by Cascade Radon, Inc. to verify that indoor radon levels were successfully reduced.

The mitigation project included the installation of an **Active Soil Depressurization (ASD) system**, designed to address the elevated radon levels identified during previous testing.

Testing Results

A 72-hour post-mitigation diagnostic test was conducted from **May 12–15, 2026**. Testing was completed while the building was assumed to be occupied using two continuous electronic radon monitors.

The results were as follows:

- **Room 123:** Average radon level of **0.2 pCi/L**
- **Room 121:** Average radon level of **0.3 pCi/L**

Both readings are **well below the U.S. EPA's recommended action level of 4.0 pCi/L**.

Conclusion

Cascade Radon, Inc. concluded that:

- The radon mitigation system was installed in accordance with applicable codes.
- Average indoor radon levels are now below the EPA's recommended action level.
- **No additional mitigation is recommended at this time.**

We are pleased with these results and remain committed to providing a safe and healthy learning environment for our students and staff.

Testing and mitigation services were provided by:

Cascade Radon, Inc.
Testing, Mitigation & Systems Design
CCB #180537 | CASCAR1927C1

--

Thank you,
Brie Windust
Business Office Assistant
Office Hours: Monday to Thursday 7:30am - 4:30 pm
Phone: 503-261-4268
www.corbett.k12.or.us
District Wide Activities Calendar



Woodard Middle School Test report (2).pdf
2478K