

Access Control Addition



Welch Public Schools

P.O. Box 189
Welch, OK 74369
Mona Stines
(918) 788-3129
mstines@welchwildcats.net

System Designs:
Jimmy Smith
Sr. Project Manager



OK # A4656262 / BICSI # 211151C
5502 N. Dennis Weaver Blvd. Suite B
Webb City, MO 64870
(918) 848-0603 Cell (417) 625-1467 Office (888) 205-6925 Company
jsmith@wyandottetech.com www.wyandottetech.com

WELCH PUBLIC SCHOOLS - ACCESS CONTROL ADDITION

FIELD HOUSE

- 1 **Single Door POE Control Unit
Keyscan**
- 1 **RP40 MultiClass SE Reader
HID**
- 1 **630 Finish 12/24V Surface Mount Heavy Duty Dual locking Electric Strike
HES**
- 1 **Request to Exit Motion Sensor
Bosch**
- 1 **Recess Mount 3/4" PTF Wide Steel Door Contact Gray
G.R.I.**
- 1 **Cat 6 Enhanced CMR VERT YELLOW
Vertical**
- 1 **Misc. EMT Conduit and Accessories
Rigid**

GYM

- 1 **4 Reader Access Control Unit
Keyscan**
- 1 **Plug-On Network Communication Adapter
Keyscan**
- 1 **AL600ULX W/ ACM8 and MOM5
Altronix**
- 2 **16V40VA Plug-In Transformer
Elk**
- 1 **3 Wire 14AWG Power Cord Bare Conductor
Bergen Industries**
- 3 **12V 8AH SLA UB-1280
Universal Battery**
- 1 **8 Outlet Surge Protector
Panamax**
- 3 **RP40 MultiClass SE Reader
HID**

- 3 630 Finish 12/24V Surface Mount Heavy Duty Dual locking Electric Strike
HES
- 3 Request to Exit Motion Sensor
Bosch
- 3 Recess Mount 3/4" PTF Wide Steel Door Contact Gray
G.R.I.
- 1 Plenum 22/6 SHLD + 22/4 + 22/2 + 18/4
Honeywell
- 1 Misc. EMT Conduit and Accessories
Rigid

BUS BARN

- 1 Single Door POE Control Unit
Keyscan
- 1 RP40 MultiClass SE Reader
HID
- 1 630 Finish 12/24V Surface Mount Heavy Duty Dual locking Electric Strike
HES
- 1 Request to Exit Motion Sensor
Bosch
- 1 Recess Mount 3/4" PTF Wide Steel Door Contact Gray
G.R.I.
- 1 Cat 6 Enhanced CMR VERT YELLOW
Vertical
- 1 Misc. EMT Conduit and Accessories
Rigid

PROJECT SUMMARY

Equipment Total	\$8,992.17
Cable & Hardware	\$15.00
Programming	\$85.00
Installation Total	\$1,530.00
Design, Project Management	\$125.00
Tax	<u>\$0.00</u>
TOTAL	\$10,747.17

Terms, Scope and Acceptance

Your satisfaction is important to us, and we plan to exceed your expectations!

This proposal is a complete package, including design, wiring, equipment, installation, and coordination of plans with architects, decorators, electricians, and cabinetmakers.

All equipment is warranted by the manufacturers. We guarantee all installation work to be free of defects for a period of one year from installation date. If service is required, we will be happy to provide you with excellent service for your system. Wyandotte Technologies assumes no responsibility for damages, either direct or consequential, that may result from accidents associated with the design, installation, and operation of the equipment listed herein. Prices contained in this proposal are valid for 30 days. Any changes to this proposal will be submitted in writing for approval.

Adequate and appropriate access should be given to the employees of Wyandotte Technologies for the areas in which the work will be completed. Any obstacles or obstructions that would inhibit Wyandotte Technologies from completing the installation should be removed prior to the installation date. Details not included in the original specifications of the work should be disclosed prior to the installation start.

Equipment Manufacturer's regularly update their product offerings. In our efforts to provide you with the very latest technology, we reserve the right to substitute the most up to date models available at the time of installation.

Terms: Billing for services and equipment provided will be submitted upon completion of the installation. We require 14 days advance notice before beginning each phase of the work. This equipment shall remain the property of Wyandotte Technologies until all installation and equipment charges have been paid in full.

Accepted By (Client)	Date	Title (Client)
Wyandotte Technologies	Date	Title

I accept this proposal and authorize the work to be initiated and accept responsibility for payments due.

Field House Fiber Replacement



Welch Public Schools

P.O. Box 189
Welch, OK 74369
Mona Stines
(918) 788-3129
mstines@welchwildcats.net

System Designs:
Jimmy Smith
Sr. Project Manager



OK # A4656262 / BICSI # 211151C
5502 N. Dennis Weaver Blvd. Suite B
Webb City, MO 64870
(918) 848-0603 Cell (417) 625-1467 Office (888) 205-6925 Company
jsmith@wyandottetech.com www.wyandottetech.com

WELCH PUBLIC SCHOOLS - FIELD HOUSE FIBER REPLACEMENT

FIELD HOUSE

1 **6 Strand OSP MM Fiber LC-LC Pre-Term w/Pull Eye 300ft
QuickTrex**

PROJECT SUMMARY

Equipment Total	\$689.97
Installation Total	\$510.00
Design, Project Management	\$125.00
Shipping & Handling	\$30.00
Tax	<u>\$0.00</u>
TOTAL	\$1,354.97

